







# TEST REPORT

CEPRI-EETC08-2020-1000 (E)

Client: Shenzhen Woer Heat-Shrinkable Material Co., Ltd.

Object: Pre-moulded straight joint for 64/110 kV XLPE cable

Type: WYJJTI2 64/110 1×1600

Test Category: Type tests



### Power Industry Quality Inspection and Test Center for Electric Equipment

CEPRI-EETC08-2020-1000(E)
Total 11 Page 1

# Catalogue

1. Catalogue	1
2. Signature Page	2
3. Test Results	3
4. Content	4
5. Appendix A Object Parameters	5
6. Appendix B The Main Test Devices	7
7. Appendix C Test Circuit Diagrams	8
8. Appendix D Waveform	9
9. Appendix E Identification of test cable	11

Test Report	Power Industry Quality Insp Center for Electric Ed	CEPRI-EETC08-2020-1000(E Total 11 Page 2			
Client	Shenzhen Woer Heat-Shrinkable Material Co. 4	Manufacturer	Shenzhen Woer Heat-Shrinkable Material Co., Ltd.		
Object	Pre-mouded straight joint for 464/110 kV-XLPE cable	Туре	WYJJTI2 64/110 1×1600		
Sampling procedure	Taken by client s用章	Serial No.	EETC08-20/08/08-101		
Test Category	Type tests	Date	2020.09.08~2020.10.14		
Requirements	<ol> <li>GB/T 11017.3—2014 Power ca their accessories for rated voltage o</li> <li>IEC 60840(Edition 5.0): 2020 accessories for rated voltages abov -Test methods and requirements</li> </ol>	of 110 kV ( $U_{\rm m}$ =126 kV Power cables with $\epsilon$	V)—Part 3: Accessories extruded insulation and their		
Conclusion	The pre-moulded straight joint of which is WYJJT12 64/110 1×1600 successfully passed the type test 60840(Edition 5.0): 2020.	taken to test by	the client's own self ha		
Note	In the event of any difference in mean English version.	ings, the Chinese repo	rt shall take priority over the		
Compiled by: 袁	牧青籽	倪玉林 73. 丰	<b>F</b>		
Checked by: 王	王	Verified by: 徐明忠	徐明忠		
Approved by: 付	村超	Date of issue: 20	20-11-03		

### Power Industry Quality Inspection and Test Center for Electric Equipment

CEPRI-EETC08-2020-1000(E) Total 11 Page 3

#### **Test Results**

No.	Item	Requirements	Results	Evaluation	
	Partial discharge test at ambient temperature	No detectable discharge exceeding the sensitivity from the test assembly at 96 kV	No detectable discharge was found at 96 kV exceeding the sensitivity of 3.28 pC	Passed	
2	Heating cycle voltage test	As per clause 1.2 of content in this report	Subjected to heating cycle voltage test, and heating cycle had been carried out 20 times	Passed	
3	Partial discharge test at high temperature	No detectable discharge exceeding the sensitivity from the test assembly at 96 kV	No detectable discharge was found at 96 kV exceeding the sensitivity of 3.28 pC	Passed	
4	Partial discharge test at ambient temperature	No detectable discharge exceeding the sensitivity from the test assembly at 96 kV	No detectable discharge was found at 96 kV exceeding the sensitivity of 3.28 pC	Passed	
5	Lightning impulse voltage test	The assembly shall withstand without failure or flashover 10 positive and 10 negative voltage impulses of 550 kV	No breakdown occurred on the test assembly at 10 positive and 10 negative impulses of 550 kV	Passed	
6	Power frequency voltage test after lightning impulse voltage test	The assembly shall be subjected to a power frequency voltage test at 160 kV for 15 min, and no breakdown of the insulation or flashover shall occurred	No breakdown occurred at 160 kV for 15 min	Passed	
7	Examination  As per clause 1.4 of content in this report		No signs of deterioration on which could affect the sample in service operation was found	Passed	

(There is no content below this page)

#### Power Industry Quality Inspection and Test Center for Electric Equipment

CEPRI-EETC08-2020-1000(E) Total 11 Page 4

#### Content

#### 1. Test methods

#### 1.1 Partial discharge tests

The tests were carried out at ambient temperature and high temperature in accordance with GB/T 3048.12 and IEC 60885-3, There shall be no detectable discharge exceeding the declared sensitivity from the test object at 96 kV. The background noise is no more than 1.64 pC during these tests.

The test voltage shall be raised gradually to and held at 112 kV for 10 s and then slowly reduced to 96 kV and the partial discharge tests were carried out at 96 kV. At high temperature the test shall be performed on the sample at a conductor temperature of  $(95\sim100)$  °C. The conductor temperature shall be maintained within the stated temperature limits for at least 2 h.

#### 1.2 Heating cycle voltage test

According to GB/T 11017.3—2014 and IEC 60840(Edition 5.0): 2020, the test assembly shall be heated by conductor current until the cable conductor reaches a temperature of  $(95\sim100)$  °C. The heating shall be applied for at least 8 h. The conductor temperature shall be maintained with in the stated temperature limits for at least 2 h of each heating period. This shall be followed by at least 16 h of natural cooling to a conductor temperature less than or equal to 30 °C or within 10 K of ambient temperature, whichever is the higher. The cycle of heating and cooling shall be carried out 20 times. During the whole of the test period a voltage of 128 kV shall be applied to the sample.

#### 1.3 Lightning impulse voltage test followed by a power frequency voltage test

The assembly shall be heated by conductor current only, until the cable conductor reaches a steady temperature of  $(95\sim100)$  °C. The conductor temperature shall be maintained within the stated temperature limits for at least 2 h.

The lightning impulse voltage shall be applied according to the GB/T 3048.13. The assembly shall withstand without failure or flashover 10 positive and 10 negative voltage impulses of 550 kV. After the lightning impulse voltage test, the test assembly shall be subjected to a power frequency voltage test at 160 kV for 15 min. No breakdown of the insulation.

#### 1.4 Examination

Examination of the accessories by dissection of a sample and, whenever possible, of the accessories by dismantling with normal or corrected vision without magnification shall reveal no signs of deterioration (e.g. electrical degradation, leakage, corrosion or harmful shrinkage) which could affect the system in service operation.

#### 2. Test data

The values of lightning impulse voltages on the test assembly after heating cycle voltage test (at high temperature, 550 kV,  $\pm 3 \%$  tolerance)

Ambient temperature: 25.0℃ Relative humidity: 61 % Barometric pressure: 0.1012 MPa

	X 10	36,86	20				7	U (	u	nit: k
Positive voltages	554	553	551	554	554	553	554	554	555	553
Negative voltages	555	549	552	553	555	553	552	554	553	553

#### Power Industry Quality Inspection and Test Center for Electric Equipment

CEPRI-EETC08-2020-1000(E) Total 11 Page 5

#### **Appendix A Object Parameters**

#### A.1 Specification of sample

#### A.1.1 Sample state

The sample was manufactured in June, 2020, and was received on August 8, 2020 at Power Cable Quality Inspection Station of Power Industry Quality Inspection and Test Center for Electric Equipment, and it was in good condition without breakage.

#### A.1.2 Related information of sample

The material of connector is copper  $T_2$ , the material used for pre-moulded unit is EPDM rubber, and the cable conductor is compacted with the connector by pressure.

#### A.1.3 Installation description

The sample to be tested has been installed by the manufacturer on a XLPE insulated single core cable with rated voltage 64/110 kV and having a cross-section of  $1600 \text{ mm}^2$ , the type and size of cable is ZA-YJLW03-Z  $64/110 \text{ l} \times 1600$ .

#### A.2 Photograph of sample




(There is no content below this page)

### Power Industry Quality Inspection and Test Center for Electric Equipment

CEPRI-EETC08-2020-1000(E) Total 11 Page 6

# A.3 The dimensions of main construction of the sample tested



# Power Industry Quality Inspection and Test Center for Electric Equipment

CEPRI-EETC08-2020-1000(E) Total 11 Page 7

### **Appendix B The Main Test Devices**

Sequ- ence	Name of the equipment and instruments Type/Size	Serial No.	Full-scale range	Uncertainty / Accuracy	Verification / Calibration authority	Term of validity	
1	RSZ-800-6-50  Corona-free series-resonant test system	204488	(0∼800) kV				
2	KKF-800-5 Power frequency voltage divider	454485	(0∼800) kV	Class 1	National Meterage Center of High Voltage and Heavy Current	2021.07.2	
3	Digital partial discharge detectot	2013-023	(0.1~999) pC	10 %	National Meterage Center of High Voltage and Heavy Current	2020.11.04	
4	CJDY-3000/600 Impulse voltage generator	01	(0∼3000) kV				
5	CJDY-3000  HV divider for impulse voltage divider measurement	001	(0∼3000) kV	Class 1	National Meterage Center of High Voltage and Heavy Current	2021.07.07	
6	HiAS1214 Digital impulse Voltage analysis system	20050512	(0∼3000) kV	Class 3	National Meterage Center of High Voltage and Heavy Current	2021.05.20	
7	272 Wet and dry bulb hygrometer	304	(0~50) ℃	General	Hubei Meteorological Metrology Station	2021.10.11	

### Power Industry Quality Inspection and Test Center for Electric Equipment

CEPRI-EETC08-2020-1000(E) Total 11 Page 8

Appendix C Test Circuit Diagrams




### Power Industry Quality Inspection and Test Center for Electric Equipment

CEPRI-EETC08-2020-1000(E) Total 11 Page 9

#### Appendix D Waveform

# D.1 Oscillograms of the impulse voltages waveform




(There is no content below this page)

### Power Industry Quality Inspection and Test Center for Electric Equipment


CEPRI-EETC08-2020-1000(E) Total 11 Page 10

## D.2 Oscillograms of partial discharges

# D.2.1 The background noise during partial discharge tests



D.2.2 The oscillogram of partial discharges at 96 kV(After heating cycle voltage test at high temperature)



# Power Industry Quality Inspection and Test Center for Electric Equipment

CEPRI-EETC08-2020-1000(E) Total 11 Page 11

# Appendix E Identification of test cable

Rated	voltage $U_0/U(U_{\rm m})$ kV	64/110 (126) kV	
Construction	Core	Single core	
	Material	Copper TR	
KEN O YES	Construction	Milliken conductor	
Conductor	Cross section	1600 mm <sup>2</sup>	
THE TO THE TO	Diameter	48.4 mm	
	Average thickness of conductor screen	2.2 mm	
Chi Co Chi Co	Material	XLPE	
Insulation	Average thickness	16.4 mm	
CO SECO	Diameter	83.9 mm	
Screen	Average thickness of insulation screen	1.4 mm	
VO CHO CO	Diameter of insulation screen	86.7 mm	
Cushion and longitudinal water impermeable barrier Material		A layer of semi-conducting elastic water impermeable swell tape and a layer of semi-conducting water impermeable swell tape	
TO SELECT	Material	Aluminum	
Corrugated metallic sheeth	Average thickness	2.4 mm	
metallic sheath	Manufacturing technology of metallic sheath	Seam welded corrugated aluminum sheat	
EE O FE O	Material	PE	
Oversheath	Average thickness	5.4 mm	
C W C	Diameter	118.3 mm	
Water Commence	Capacitance	262 pF/m	
Outer diam	eter of complete cable	118.3 mm	
Ma	urking of cable	江苏中超电缆股份有限公司 ZA-YJLW03-Z 64/110 kV 1×1600 2020 年 7 月 ZC2005A1701B	